

1060654

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,314-0000
NE SW NE SEC. 20, T 16 S, R 16 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name ~~XXXX~~ "C" Well # 1
County Rush 115.44

Operator: Thunderbird Drilling, Inc.
Name & Address: P. O. Box 18407
Wichita, KS 67218

Well Total Depth 3552 Arbuckle feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131
Address P. O. Box 18407, Wichita, KS 67218

Company to plug at: Hour: 5:00 pm Day: 3 Month: September Year: 19 85

Plugging proposal received from Ed Cook

(company name) Thunderbird (phone) 316-685-1441

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1080-1110' Elevation 1963 KB

1st plug into the Arbuckle with 40 sx cement

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' out of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 pm Day: 3 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3550' with 40 sx cement

2nd plug at 1100' with 50 sx cement, 3rd plug at 370' with 50 sx cement, 4th & 5th plugs -
solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to
circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

I (XXX) did not observe this plugging.

DATE SEP 10 1985

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 10016