

1030340

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,925-0000

SE SW NW, SEC. 10, T 16 S, R 16 W/R

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Urban Well # 1

Operator: Woodman-Iannitti Oil Co.

County Rush 115.70

Name & Address Box 308

Well Total Depth 3560 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1068

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 29 Month: November Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 4 1/2" set at 3559 Perfs from 3510-12

1st plug sand back to 3460' and dump 4 sx cement on top of sand through bailer.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 29 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3559' Perfs from 3510-12'

1st plug sanded back to 3460' and dumped 4 sx cement on top of sand through bailer.

2nd plug squeezed well with 30 sx gel, released 8 5/8" rubber plug and pumped 170 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 550 psi

DEC 05 1984

Remarks: Recovered 3000' of 4 1/2" casing. Used 60/40 Pozmix 2% gel in 10% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVESTIGATED

1 (did / did not) observe this plugging.

DATE 12-12-84

Signed Steve Shumant
(TECHNICIAN)

INV. NO. 5933