

1 030442

15-165-19002-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OWWO Comp. 5-27-37

SW SW SW , SEC. 14 , T 16 S, R 16 W/4

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6867

Lease Name Schippers Well # 1

Operator: LaVern Steinle

County Rush 115.67

Name & Address 624 East 3rd

Well Total Depth 3559 feet

Russell, KS 67665

Conductor Pipe: Size 15 1/2 feet 21

Surface Casing: Size 12 1/2 feet 485

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 9:00 am Day: 19 Month: June Year: 19 85

Plugging proposal received from LaVern Steinle

(company name) LaVern Steinle (phone) 913-483-3905

were: 10" at 1054', 8 5/8" at 2835', 7" at 3249' - recovered 2658 6-20-40, 7" liner from 820' to surface - circulated, Anhydrite at 1075', Cedar Hills at 550', Base Dakota at 300', Cement from 3538-3523, bit and collar at approx. 2500'

1981- 12 1/2"-8 5/8" annulus squeezed three times with 325 sx cement, 7" ran in hole to 820' and circulated to surface.

6-19-85 - pumped 200 sx cement down 7" and fell to 300' in 2 hours. Pressured up

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 am Day: 19 Month: June Year: 19 85

ACTUAL PLUGGING REPORT CONTINUED -

12 1/2"-8 5/8" annulus with immediate pressure. Wait two days and fill 7" from 300' to surface with cement.

JUN 21 1985

Steve Durrant

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 6-25-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 8689