

To: 1080016

API NUMBER 15-203-20,119-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

App. SW NW NE, SEC. 28, T 19 S, R 36 W/E
4080 feet from S section line
2150 feet from E section line

TECHNICIAN'S PLUGGING REPORT

2-15

Operator License # 5506
Operator: Woolsey Petroleum Corporation
Name & Address: 107 N. Market, #600
Wichita, KS 67202

Lease Name Shimanek Well # 1
County Wichita
Well Total Depth 5800 186.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address _____

Company to plug at: Hour: 12 p.m. Day: 15 Month: 2 Year: 19 96

Plugging proposal received from Vernon Schrant

(company name) Woolsey Petroleum Corp. (phone) 316-886-5606

logs: 4 1/2" at 3398' w/450 sx cement, 250 sx ASC, PBTD 3357', Perfs at 3282-88, CIBP @ 3250',
Perfs at 2744-54'

1st plug set CIBP at 2660' with 4 sx cement on top,

2nd plug pump 5 sx gel and 20 sx cement and 2 sx gel at 775',

3rd plug pull to 270' and pump 40 sx cement, 4th plug pull to 40' and circulate cement w/10 sx.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2660' with 4 sx cement on top,

2nd plug pumped 5 sx gel and 20 sx cement and 2 sx gel at 775',

3rd plug pulled to 270' and pumped 40 sx cement,

4th plug pulled to 40' and circulated cement with 10 sx.

RECEIVED
KANSAS CORP COMM
FEB 19 A 9:39
2-19-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 816' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-28-96

INV. NO. 44915

Signed Kevin D. Strube (TECHNICIAN)