

1050004

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-203-20,071-0000

SF SE NW Sec. 27, T 19 S, R 36 W 1/2

2490 feet from N 1/4 section line

2490 feet from W 1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name HARRIS Well # 1-27

Operator: Helmerich + Payne Inc.  
Name & Address: P.O. Box 558  
Garden City, Kansas  
67846

County Wichita

Well Total Depth 5600 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 481

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling License Number 5104

Address Box 1413 Great Bend, Kansas 67530

Company to plug at: Hour: 10:00 pm Day: 14 Month: September Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Leroy Baron

(company name) Blue Goose Drilling (phone) \_\_\_\_\_

were: To use 60/40 poz mix 2% gel 3% cc

1st plug @ 2370' w/50sx, 2nd plug @ 1020' w/50sx

3rd plug @ 540' w/40sx, 4th plug @ 40' w/

solid Bridge Plug + 10sx - Circulate 15sx in  
Rathole

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:00 am Day: 15 Month: September Year: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Dowell pumped the cement

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1983  
9-22-83  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED

DATE 9-28-83

INV. NO. 5538-LW

Signed Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82