

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20028-00-00
Spot: CSEnw Sec/Twnshp/Rge: 35-18S-38W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease/Unit Name: BAUM Well Number: 1
County: WICHITA Total Vertical Depth: 3120 feet

Operator License No.: 31655
Op Name: MCELVAIN ENERGY
Address: RR 1, BOX 223
DELAWARE, OK 74027

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 346 WITH 250 SX CMT
Production: Size 4.5 feet: 3120 WITH 125 SX CMT
Liner: Size feet: 101.40

Well Type: GAS UIC Docket No: Date/Time to Plug: 07/31/2001 9:30 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: BRAD SEIB Company: PLAINS INC Phone: (785) 798-3995

Proposed Plugging Method: RUN TUBING TO 2300' & PUMP 70 SX CMT WITH 300# HULLS. PULL UP TO 1500' & CIRCULATE CMT TO SURFACE. PULL TUBING OUT OF HOLE AND PUMP 80 SX CMT DOWN 4 1/2". USE 150 SX TO CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/31/2001 2:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2804-20'. ON 7/27/01 SHOT TUBING OFF AT 2400'. PULLED TUBING OUT OF HOLE. ON 7/31/01 PERFORATED 4 1/2" @ 1400'. RAN TUBING TO 2310'. PUMPED 70 SX CMT WITH 300# HULLS. PULLED UP TO 1500'. CIRCULATED TO SURFACE WITH 70 SX CMT. PULLED TUBING OUT OF HOLE. PUMPED DOWN 4 1/2" 80 SX CMT @ 800#. SHUT IN AT 500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 150 SX CMT @ 200#. SHUT IN AT 200#.

8-2-01
2002060178

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

INVOICED

DATE 8-3-01

INV. NO. 2002060178

District: 01

Signed Kevin D Strube
(TECHNICIAN)

AUG 01 2001

Form 

