

1080219

TO: STATE CORPORATION COMMISSION

9-30

API NUMBER 15-203-20,039-0000
C SW SEC. 34, T 18 S, R 38 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HOLLAND WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY WICHITA

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 3250 FEET

OPERATOR: KCC FEE FUND #9900-17-001 PRODUCTION CSG: SIZE 5 1/2 " FEET 3250

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8 " FEET 337'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING COMPANY, INC LICENSE NUMBER N/A

ADDRESS PO BOX 628, GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 12:20 PM DAY: 30 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEVIN STRUBE

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: PERFS AT 3019-3188

PUMP 500# HULLS, 25 SX CEMENT, DISPLACE TO 2960'. PERFORATE @ 1400', PUMP 80 SX OVER

CASING VOLUME. PRESSURE TEST 8 5/8" X 5 1/2" ANNULAS TO 500# WITH 50 SX CEMENT. RESTORE LOCATION

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 29 MONTH: 09 YEAR: 1998
HOUR: 1:15 PM DAY: 30 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG ALLIED PUMPED 250# HULLS, 25 SX CEMENT, DISPLACED TO 2625'. MAXIMUM PSI PRESSURE 1000#. SHUT IN AT 800#. LOG-TECH OF KANSAS PERFORATED AT 1400' WITH 2 HOLES.

2ND PLUG ON 9/30/98 ALLIED PUMPED DOWN 5 1/2" CASING, TOOK INJECTION RATE @ 3 1/2 BBL PER MINUTE @ 500#. STARTED CEMENT, 60/40 6% , PUMPED 170 SX. 500# MAXIMUM PRESSURE. SHUT IN AT

300#. 3RD PLUG PUMPED 65 SX CEMENT DOWN 8 5/8" X 5 1/2" ANNULAS. SHUT IN AT 100#.

REMARKS: TOTAL CEMENT: 25 SX ON BOTTOM & 235 SX ON REMAINDER OF PLUG.
USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube (TECHNICIAN)

10-31-98 86/18-0