

To: 1 060165 5-8
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-203-20,100-0000
150' SE of
SE SW, SEC. 15, T. 18 S, R. 38 W X
550 feet from S section line
3190 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5316
Operator: Falcon Exploration, Inc.
Name: 155 N. Market, Ste. 1010
Address: Wichita, KS 67202

Lease Name Oldham Well # 2
County Wichita 178.68
Well Total Depth 5498 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 5 Year: 19 93

Plugging proposal received from Harold Maley
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2473-2491'
1st plug at 2550' with 50 sx cement, 2nd plug at 1500' with 50 sx cement,
3rd plug at 750' with 50 sx cement, 4th plug at 380' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by _____ Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2550' with 50 sx cement,
2nd plug at 1500' with 50 sx cement,
3rd plug at 750' with 50 sx cement,
4th plug at 380' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 5-17-93
INV. NO. 37724
5-8

Signed Case Morris (TECHNICIAN)
Rec'd 5-17-93