

15-055-20184-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 55' NW C SW/4, SEC. 9, T 25 S, R 31 W 2E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15--Drilled in 1975

TECHNICIAN'S PLUGGING REPORT  
1350 feet from S section line  
3985 feet from E section line

RECEIVED  
12-05-88

Operator License # 9151 Lease Name Reed Well # 2

Operator: Marden Production Company County Finney 83.69

Name & Address P.O. Box 706 Edmond, OK 73083-0706  
Well Total Depth 2575 feet

Conductor Pipe: Size feet 1800

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rocket Well Service License Number

Address

Company to plug at: Hour: 10 a.m. Day: 2 Month: 12 Year: 1988

Plugging proposal received from Dave Williams

(company name) Marden Production Company (phone) 316-793-5685

were: 4 1/2" at 2570' Perfs at 2518-2525'

1st plug at 497' with 50 sx cement pump through tubing filling 4 1/2" to 0',

2nd plug pump 150 sx cement down 4 1/2" & 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 2 Month: 12 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 497' with 50 sx cement pumped through tubing, filling 4 1/2" to 0',

2nd plug pumped 150 sx cement down 4 1/2" & 8 5/8" annulus. Maximum pressure 300 psi and shut in 100 psi.

NOTE: Packer sanded off at 2500', holes from 1400-1800' squeezed and tested and didn't hold. Squeezed with 80 sx cement again and it wouldn't take cement the second time. TOC at 1200'.

Remarks: Used 60/40 Pozmix 4% gel by B.J. Titan. No casing recovery (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Paul A. Luthis (TECHNICIAN)

DATE DEC 8 1988

INV. NO. 23267