

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20138-00-00
Spot: CE2NE Sec/Twnshp/Rge: 12-20S-40W
1320 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: WATSON E Well Number: 1
County: GREELEY Total Vertical Depth: 2869 feet

Operator License No.: 32340
Op Name: BLUEGRASS ENERGY, INC.
Address: 5727 S. LEWIS, STE 720
TULSA, OK 74105

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 260 WITH 200 SX CMT
Production: Size 4.5 feet: 2869 WITH 500 SX CMT
Liner: Size feet: \$ 93.24

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/17/2001 9:20 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: BLUEGRASS ENERGY Phone: (316) 376-8190

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING 400# HULLS & 125 SX CMT. PUMP DOWN 8 5/8" X 4 1/2" ANNULUS 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/17/2001 10:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2863'. PERFS AT 2808-21'. ALLIED PUMPED DOWN 4 1/2" CASING 400# HULLS & 125 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 10 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

INVOICED
DATE 4-27-01
INV. NO. 2001061731

RECEIVED
APR 27 2001
4-27-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

APR 23 2001

Form CP-23

MP