

X 020176  
1

8-31-88 15-071-20007-0000  
3171

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/13/82

C SW NE, SEC. 14, T 20 S, R 40 W/E

3300 feet from S section line

1980 feet from E section line

Lease Name Spears Well # 1

County Greeley 92.30

Well Total Depth 2840 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 415

TECHNICIAN'S PLUGGING REPORT

Operator License # 9922

Operator: Hughes Seewald

Name & Address % Higginbottom Engineering, Inc.

P.O. Box 2587

Liberal, KS 67905

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 31 Month: 8 Year: 19 88

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 2840' PBTD 2838' Perfs at 2828-36'

1st plug pump bottom with 2 sx hulls and 20 sx cement,

2nd plug at 1500' with 40 sx cement,

3rd plug at 450' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 31 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug ran 2 sx hulls and 20 sx cement to plug perfs,

2nd plug pumped 40 sx cement at 1540',

3rd plug pumped 40 sx cement at 430',

4th plug pumped 11 sx cement at 40-0'.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1540' of 4 1/2" casing. (Additional description is necessary, use BACK of this form.)

INVOICED

(did /XXXXXX) observe this plugging.

DATE 9-9-88

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 22204