

1 051999

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,645 - 0000

C N/2 , SEC. 18 , T 20 S, R 40 W/E

1320 feet from N section line
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30606

Lease Name Mooney Well #1-18

Operator: Murfin Drilling Co., Inc./

County Greeley 100.75

Name:

Well Total Depth 3100 feet

Address Trident Energy Corp.

Conductor Pipe: Size feet

250 N. Water, Ste. 300

Surface Casing: Size 8 5/8 feet 358

Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 7:45 a.m. Day: 6 Month: 1 Year: 19 96

Plugging proposal received from Keith Van Pelt

(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2412-31'

1st plug at 2430' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:45 a.m. Day: 6 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2430' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 390' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION
JAN 9 1996
1-9-96

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 23 1996

Signed Richard W Lacey (TECHNICIAN)

44692