

7-4

To: 1 031457  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-071-20,672-0000  
C SE NE, SEC. 20, T 20 S, R 40 W/E  
1980 feet from N X section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4894  
Operator: Horseshoe Operating, Inc.  
Name:  
Address 500 W. Texas, Ste. 1190  
Midland, TX 79701

Lease Name Panning Well # 2  
County Greeley 92.46  
Well Total Depth 2845 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 274

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co., Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 4 Month: 7 Year: 19 97

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Co., Inc. (phone) 316-267-3241

purpose: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2411-30'

1st plug at 2430' with 50 sx cement, 2nd plug at 1390' with 80 sx cement,

3rd plug at 700' with 25 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:30 a.m. Day: 4 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2430' with 50 sx cement,

2nd plug at 1390' with 80 sx cement, 3rd plug at 700' with 25 sx cement,

4th plug at 300' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(Additional description is necessary, use BACK of this form.)

DATE (XXX / did not) observe this plugging.

INV. NO. 48545

Signed Steve Durrant (TECHNICIAN)

Handwritten initials: Vb-hl-V