

1 090063

3-20

101-21,574 -0000

236

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 11, T 16 S, R 30 W/EX

330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 N. Market, Suite 205
Wichita, KS 67202

Lease Name Price "W" Well # 1
County Lane Lane 146.57
Well Total Depth 4510 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 3:15 p.m. Day: 20 Month: 3 Year: 19 91

Plugging proposal received from Doyle Faulkers
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2133-63'
1st plug at 2170' with 50 sx cement, 2nd plug at 1700' with 80 sx cement,
3rd plug at 850' with 50 sx cement, 4th plug at 310' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent: All Part None X

Operations Completed: Hour: 6:15 p.m. Day: 20 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2170' with 50 sx cement,
2nd plug at 1700' with 80 sx cement,
3rd plug at 850' with 50 sx cement,
4th plug at 310' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-9-91
INV. NO. 31422

RECEIVED
MAR 26 1991
3-26-91
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 3 - 12 - 1991
month day year

SE. SE. SW. Sec 11. Twp 16S. S, Rg 30. East
West

OPERATOR: License # 5123
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Don Beauchamp
Phone: 262-8427

330 feet from South line of Section
2970 feet from East line of Section

(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5123
Name: Company Tools

County: Lane
Lease Name: Price 1W1 Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Lansing - Mississippian
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2742 feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 100
Depth to bottom of usable water: 1225
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 250
Length of Conductor pipe required: None
Projected Total Depth: 4500
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond other

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

DWR Permit #: _____
Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

Directional, Deviated or Horizontal
If yes, total depth location: _____

MAR 26 1991 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Foulkeas
SPUD DATE 3-11-91 INIT. GB
LENGTH SURFACE PLANNED 250' 0.18g
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? N SIZE HOLE
SURFACE PIPE 8 7/8 @ 278 CONDUCTOR
ANHYDRITE T- 2133 B- 2163 ELEVATION
TD 4510' FORMATION ms
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2170 Ft. W/ 50SX
1/2 Base Anyh. @ 1700 Ft. W/ 80 SX
1/2, 1/2 Plug @ 850 Ft. W/ 50 SX
Bottom Surface @ 310 Ft. W/ 50SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SM DATE 3-18-91 Hauling
TYPE OF CEMENT 60/40 6% 1/4 Flb Seal 1m+As
STARTING TIME 3:15 (AM/PM) DATE 3-28-91
COMPLETION TIME 6:15 (AM/PM) DATE 3-28-91
CEMENT COMPANY Alfred