

1060252

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,995 -0000

NW NE NE, SEC. 11, T 16 S, R 30 W/E
4950 feet North from SE corner
1020 feet West from SE corner

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name York 'KK' Well # 1

Operator: Donald C. Slawson

County Lane

Name & Address 200 Douglas Building

Well Total Depth 4470 ^{145.28} feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 28 Month: June Year: 19 84

Plugging proposal received from Jim Loftis

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement

2nd plug at 1600' with 40 sx cement

3rd plug at 440' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 pm Day: 28 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1600' with 40 sx

cement, 3rd plug at 440' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form)

Stamp: JUL 06 1984
7-6-84
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(If additional description is necessary, use BACK of this form) observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

DATE 7-16-84

INV. NO. 2521

JUL 17 1984 AUG 3 1984