

1030284

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,152-0000
C NE NE, SEC. 1, T 18 S, R 31 W/E
4620 feet from XXX SE Corner of section line
660 feet from XXX SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Ramsey Well # 1

Operator: Thunderbird Drilling, Inc.

County Scott

Name: Thunderbird Drilling, Inc.

Address 7701 E. Kellogg, Suite 780

Well Total Depth 4690 152.43 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 21 Month: September Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4393' PBDT 4200' Perfs at 4164-67' 4214-16' 4246-48'

1st plug sand back to 4095' and dump 5 sx cement on top of sand

2nd plug squeeze well with 2 sx hulls, 10 sx gel 50 sx cement, 10 sx gel, 1 sack hulls release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by Steve Bennett
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00 am Day: 21 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4393' PBDT 4200' Perfs 4164-67' 4214-16' 4246-48'

1st plug sanded back to 4095' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in pressure 200 psi

OCT 09 1984
10-9-84

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve Bennett
(TECHNICIAN)

DATE 10-11-84

INV. NO. 4047