

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1963
10-21-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Publishers Petroleum Company,

Complete Address: 500 North Broadway, Oklahoma City, Oklahoma.

Lease Name Kelly Unit Well No. 1

Location NW-SE Sec. 5 Twp. 19 Rge. (E) (W) 40

County Greeley Total Depth 2940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractors: Sargent's Casing Pulling Company,

Address: 121 West 9th, Liberal, Kansas. License No. 511

Operation Completed: Hour 10:00AM Day 14 Month 10 Year 1963

The Above well was plugged as follows:

174'--8 5/8" Surface pipe, cement circulated.

2940'--4 1/2" cemented. Top perforations @ 2933'.

Squeezed bottom of well from TD to 2833' with 10 Sx cement. Pulled 4 1/2"

to 217' and displaced 25 Sx cement from 217' to 137'. Pulled 4 1/2", set

rock bridge from 35' to 30' and 10 Sx cement to bottom of cellar.

(Recovered 1608' 4 1/2" Ca sing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10/21/63

INV. NO. 7921-W