

K
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dorchester Exploration, Incorporated,
Complete Address 1201 Vaughn Building, Midland, Texas.
Lease Name Grimes Well No. 1
Location CSW/4 Sec. 11 Twp. 20 Rge. (E) (W) 40
County Greeley Total Depth 2858'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Sargent's Casing Pulling Service,
Address 620 So. Lincoln, Liberal, Kansas. License No. 511
Operation Completed: Hour 10:00 AM Day 25 Month 1 Year 1974

The above well was plugged as follows:

420'--8 5/8" Surface casing, cement circulated.
2857'--1 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 2250'.
Top perforations @ 2740'.
Pumped 1 sack of hulls followed by 20 Sx. cement and plug to bottom, followed with
wire line and stopped plug @ 2600'. Pulled 4 1/2" casing to 475' and displaced 40 Sx.
cement thru 4 1/2" casing. Pulled 4 1/2". set bridge @ 40' with 1/2 sack hulls and 10 Sx.
cement to bottom of cellar. (Recovered 2300' 4 1/2" casing).

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1974
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 2/5/74
INV. NO. 8498-W

Signed: W. J. D. Scholtz
Well Plugging Supervisor