

15-071-00004-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONTO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, KansasAPR 27 1961
4.27-61
CONSERVATION DIVISION
Wichita, KansasFile No. _____ County: Greely
Location: Ne Ne Sw Sec. 24 Twp. 20 Rge. 40 (E) (W)
Name of Field: _____ Total Depth: 2892

I have this date completed supervision of plugging of:

Lease Name: Natson Well No. 1Operator's Full Name: Kans Nebr Nat Gas CoComplete Address: 300 N St Joseph St - Hastings NebrPlugging Contractor: Southwest Casing Pulling CoAddress: Great Bend Kan. License No. _____Oil Well ☒ Gas Well ☒ Input Well _____ SWD Well _____ D & A ☒

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No ☒

If yes how long? _____ Reason: _____

Operation Completed: Hour 10 PM Day 17 Month April Year 1961

The above well was plugged as follows:

T.B. 2892' - 8 5/8" set at 289 - 5 1/2" set at 2892' - Perfs at 2834
Sand to 2824' topped with 4 sack cement, dumped
with dump bailer. Shot 5 1/2" at 2251 and pulled
same to 600' and circulated hole with mud from
neighboring drilling rig. Pulled pipe out of hole and
built bridge at 280' and displaced 20 sack cement. Mud
to 40', built bridge and displaced 12 sack cement,
cementing to base of cellar.

Signed: Herbert P. Leiker
Conservation Division AgentReviewed: Harold Hoesis
Field Supervisor

Remarks:

INVOICED

DATE 5/12/61INV. NO. 3089-W