

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 1 - 1974
4-1-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company,

Complete Address 918 Lamar Street, Wichita Falls, Texas.

Lease Name Dierks Well No. 1

Location CSE-SW Sec. 26 Twp. 19 Rge. (E) (W) 38

County Wichita Total Depth 2812' 2815'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dowell Division-Dowell Chemical Co.,

Address Box #525, Ulysses, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 21 Month 3 Year 1974

The above well was plugged as follows:

335'--10 3/4" Surface casing, cement circulated.

2679'--7" OD casing cemented on bottom with 125 Sx. Open hole completion.

Set Welex wire line bridge plug @ 1200' and 6' cement on top with dump bailer. Shot

off 7" casing @ 650', pulled 1 joint and displaced 150 Sx. cement thru 7" casing to

base of surface casing. Pulled 7" casing, set bridge and 6' cement to bottom of

cellar. Cut off Surface casing 3' below ground level and welded on steel cap.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. F. J. [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8840-W