

70
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1964
8-31-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco, Incorporated.

Complete Address: 614 Bitting Building, Wichita, Kansas.

Lease Name J. W. Roberts Well No. 1

Location CNW-NW Sec. 26 Twp. 19 Rge. (E) (W) 38

County Wichita Total Depth 5356

Abandoned Oil Well Gas Well Input Well SWD Well D & A E

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 10:15AM Day 23 Month 8 Year 1964

The Above well was plugged as follows:

290'--8 5/8 Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 1100' and displaced 30 Sx. cement thru DP.

Heavy mud to 600', set plug and displaced 30 Sx. cement thru DP. Heavy mud to 300', set

plug with 1/2 sack hulls and displaced 30 Sx. cement thru DP. Heavy mud to 40', set plug

with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

(Cementing operations performed by Halliburton Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 9/1/64
INV. NO. 9450-W