

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 - 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company.

Complete Address 918 Lamar Street, Wichita Falls, Texas.

Lease Name Foster Well No. 1

Location CNE-NE Sec. 6 Twp. 19 Rge. (E) (W) 37

County Wichita Total Depth 2920'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Dowell,

Address Box #525, Ulysses, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 8:00 PM Day 20 Month 3 Year 1974

The above well was plugged as follows:

311'--8 5/8" Surface casing, cement circulated.  
2920'--4 1/2" casing cemented on bottom with 175 Sx. Top perforations from 2807' to 2809'.

Set Welex wire line plug in 4 1/2" @ 1200' and 10' cement with dump bailer on top of plug. Shot 4 1/2" casing @ 800', pulled 1 joint and displaced 200 Sx. cement thru 4 1/2" to base of surface. Pulled 4 1/2" casing built bridge and 10' cement to base of cellar.

Welded steel cap on 8 5/8" surface casing 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel  
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8843-W