

15-203-20010-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company,

Complete Address 918 Lamar Street, Wichita Falls, Texas.

Lease Name Nuss Well No. 1

Location CNW-NW Sec. 1 Twp. 18 Rge. (E) (W) 37

County Wichita Total Depth 2842'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dowell Division, Dowell Chemical Co.,

Address Box #525, Ulysses, Kansas. License No.       

Operation Completed: Hour 5:30 PM Day 18 Month 3 Year 1974

The above well was plugged as follows:

310'--10 3/4" Surface casing, cement circulated.

2726'--7" OD casing cemented on bottom with 125 Sx. Open Hole Completion.

Set 7" Welex wire line bridge plug @2359' and 6' cement on top with wire line dump

bailer. Shot 7" casing @ 800', pulled 1 joint and displaced 250 Sx. cement thru 7"

to base of surface. Pulled 7" casing, set bridge and 10' cement to bottom of cellar.

Cut off 10 3/4" casing and welded steel cap on top.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8845-W