



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company,  
Complete Address 918 Lamar Street, Wichita Falls, Texas.  
Lease Name Evans Well No. 1  
Location CNE-NE Sec. 27 Twp. 18 Rge. (E) (W) 37  
County Wichita Total Depth 3035'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Dowell Division-Dowell Chemical Co.,  
Address Box #525, Ulysses, Kansas. License No.         
Operation Completed: Hour 12:00 M Day 20 Month 3 Year 1974

The above well was plugged as follows:

310'--8 5/8" Surface casing, cement circulated.  
3012'--4 1/2" casing cemented on bottom with 200 Sx. Top perforations from 2773' to 2784'.  
Set Welex wire line bridge plug in 4 1/2" casing @ 2400' and 10' cement on top with dump bailer. Shot 4 1/2" @ 820', pulled 1 joint and displaced 200 Sx. cement thru 4 1/2" to base of surface casing, Pulled 4 1/2", set bridge and 10' cement to bottom of cellar.  
Cut off 8 5/8" surface casing 3' below ground level and welded on steel cap.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels  
Well Plugging Supervisor

INVOICED

DATE 4/2/74  
INV. NO. 8841-W