


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Wilson County, Sec. 7 Twp. 28 Rge. 17 E
Location as "NE/CNW/SW" or footage from lines
NW SE 165' SNL 495' WEL
Lease Owner Ollamy Program
Lease Name O. Larson Well No. 2-8
Office Address P.O. Box 707 Chanute, KS. 66720
Character of Well (Completed as Oil, Gas or Dry Hole)
Oil



Locate well correctly on above Section Plat

Date Well completed 12/14/81 19
Application for plugging filed 8/30/82 19
Application for plugging approved 9/02/82 19
Plugging commenced 9/21/82 19
Plugging completed 9/21/82 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Andy Reed
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fl was placed and the method or methods used in introducing it into the hold. If cement or ot plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged 15 sacks on bottom, 90 sacks on top to 8 5/8
6 3/4 hole 350' to surface
Casing was 4 1/2" Had Cornish shoot it off at 613'
After this, circulated 350' to surface
105 sacks total used

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Falcon Oilfield Services, Inc.

STATE OF Kansas COUNTY OF Neosho, ss.
Carolyn J. Russell (employee of ~~XXXXXX~~ or ~~XXXXXXXXXXXX~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carolyn J. Russell Secretary
P. O. Box 707 Chanute, KS. 66720
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1982

My commission expires April 21, 1986

Marilyn J. James
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1982
CONSERVATION DIVISION
Wichita, Kansas

Date 12-10 81 Tour Worked _____
 Operator OLLAMY Contractor Phoenix
 Address Chanute Box 707 Address Chanute, Kans. Box 260
 Lease LARSON Well # OLL-1-7 County Wilson State KANS Legal _____

Formations	from	to	Formations	from	to
Lime	420	428			
shale	428	493			
Lime	493	530			
shale	530	613			
broken lime w/ shale streaks	613	647			
shale	647	753			
Lime	753	768			
shale break	768	776			
lime	776	776			
shale	776	800			

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 1 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Total Footage Drilled _____ Total Footage Cored _____
 Mud Used Air Cement Used _____
 Bits Used, Size and Type 7"
 Rig Time Charged to Operator—Detail— _____

Total JTS Drill Pipe on Location 61 Total in Hole 40
 Total Drill Collars on Location 0 Total in Hole 0 Footage _____
 Cased—from 0 to 50 Size 8 7/8 Weight _____
 Detail Accidents or Injuries—Remarks—Detail Repairs _____

Driller Red Hrs. Helper KEN
 Helper Jan Hrs. Helper _____
 News-Standard, Chanute, Ks. 66720

Date 12-11-81 Tour Worked _____
 Operator OLLAMY Contractor Phoenix Drilling
 Address Box #707 Chanute Address Box #260 Chanute
 Lease LARSON Well # OLL-1-7 County Wilson State Kans. Legal 7-28-170

Formations	from	to	Formations	from	to
shale	800	816			
Lime	816	837			
shale	837	846			
LIME	846	852			
shale	852	856			
sand w/light show	856	872			
shale & sandy shale	872	994			
SAND w/slight odor	994	1010			
shale	1010	1015			
sand w/odor	1015	1020			
WATER SAND	1020	1036			
shale	1036	1050			
WATER SAND	1050	1060			

RECEIVED
 STATE CONSERVATION COMMISSION
 SFP 1 1982
 CONSERVATION DIVISION
 Wichita, Kansas

Total Footage Drilled _____ Total Footage Cored _____
 Mud Used Air Cement Used _____
 Bits Used, Size and Type 7"
 Rig Time Charged to Operator--Detail-- _____

Total JTS Drill Pipe on Location 61 Total in Hole 53
 Total Drill Collars on Location _____ Total in Hole _____ Footage 1060
 Cased--from 0 to 50 Size 8 7/8 Weight _____
 Detail Accidents or Injuries--Remarks--Detail Repairs watered out with 7" hammer bit

Driller Red Hrs. Helper Ken Hr. _____
 Helper Don Hrs. Helper _____ Hr. _____
 News-Standard, Chanute, Ks. 66720 NSCO-1714

