

To: 1 050-803
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APR 30 1987

API NUMBER 15-101-21,379-0000
150' E C
N/2 N/2 SW SEC. 10, T 16 S, R 30 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation
Name:
Address 400 One Main Place
Wichita, KS 67202

2310 feet from S section line

3810 feet from E section line

Lease Name Watt Well # 1

County Lane 144.63

Well Total Depth 4450 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 30 Month: 4 Year: 1987

Plugging proposal received from Baxter Matt

(company name) H-30 Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2708' GL
Anhydrite 2119-51'

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 30' below base of surface pipe with 50 sx cement,

4th plug at 0-40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8 a.m. Day: 30 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 270' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-27-87

INV. NO. 16996

JUN 1 1 1987

Signed

Richard W. Lacey
(TECHNICIAN)

RECEIVED

STATE CORPORATION COMMISSION

MAY 27 7 5-26-87

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84