

1031254

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,630-00-01

TECHNICIAN'S PLUGGING REPORT

5011

Operator License #

Operator: Viking Resources, Inc.

Name & Address: 105 S. Broadway, Ste. 1040

Wichita, KS 67202

NE SW NW, SEC. 9, T 16 S, R 30 W/E

1650 feet from NS section line

990 feet from W/E section line

Lease Name Doll Well # 1 OWNO

County Lane

Well Total Depth 4451 144.65 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Co. Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 28 Month: 10 Year: 19 93

Plugging proposal received from Doyle Folkerts

(company name) Pickrell Drilling Co. Inc. (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2150'

1st plug at 2150' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,

3rd plug at 675' with 40 sx cement, 4th plug at 350' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1:30 p.m. Day: 28 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1320' with 80 sx cement,

3rd plug at 675' with 40 sx cement,

4th plug at 350' with 50 sx cement,

5th plug at 40' with solid bridge plug and 1 sx hulls and 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

INVOICED
Additional description is necessary, use BACK of this form. Wichita, KansasI (did / ~~XXXXXX~~) observe this plugging.

DATE 11-8-93

INV. NO. 39155

10-28 DEC 30 1993

Signed Steve Fluorant
(TECHNICIAN)RECEIVED
STATE CORPORATION COMMISSION

NOV 01 1993

CONSERVATION DIVISION
WICHITA, KANSASCONSERVATION DIVISION
WICHITA, KANSAS