

To: 1 031216
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-19 API NUMBER 15- 101-21,630 - 0000 265

NE SW NW, SEC. 9, T 16 S, R 30 W/E
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Operator: Ensign Operating Co.
Name & Address: 621 17th St., Ste. 1800
Denver, CO 80293

Lease Name Doll Family Trust Well # 1-9

County Lane 144.62

Well Total Depth 4450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 19 Month: 9 Year: 19 92

Plugging proposal received from Herb Brady

(company name) Murfin Drilling (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2081'

1st plug at 2140' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8 a.m. Day: 19 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

I (do not) observe this plugging.

DATE 10-13-92

INV. NO. 34337

Signed Steve Durrant (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
9-23-92
SEP 23 1992

CONSERVATION DIVISION
Wichita, Kansas