

To: 1 090346 10-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,664-0000
E/2 SE NW, SEC. 4, T 16 S, R 30 W X
3300 feet from S section line
2310 feet from W X section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name:
Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name York "L" Well # 1
County Lane 158.60
Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 23 Month: 10 Year: 19 93

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2178'
1st plug at 2180' with 50 sx cement, 2nd plug at 1275' with 80 sx cement,
3rd plug at 630' with 40 sx cement, 4th plug at 280' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X


Operations Completed: Hour: 3 p.m. Day: 23 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,
2nd plug at 1275' with 80 sx cement,
3rd plug at 630' with 40 sx cement,
4th plug at 280' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1993
10-29-93
Conservation Division
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(Additional description is necessary, use BACK of this form.)

INVOICED
I (XXX) / did not observe this plugging.
DATE NOV 05 1993
INV. NO. 39144

Signed 
(TECHNICIAN)