

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20485-00-00  
Spot: CNENESW Sec/Twnshp/Rge: 22-16S-16W  
2970 feet from N Section Line, 2310 feet from W Section Line  
Lease/Unit Name: DIETZ Well Number: 1  
County: RUSH Total Vertical Depth: 3550 feet

Operator License No.: 5146  
Op Name: RAINS & WILLIAMSON OIL CO., INC.  
Address: 220 WEST DOUGLAS, STE 200  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 1041 WITH 450 SX CMT  
Production: Size 5.5 feet: 3546 WITH 150 SX CMT  
Liner: Size feet:

11538

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/07/2001 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOE ROGERS Company: ALLIED CEMENT COMPANY Phone: (316) 793-5861

Proposed Plugging Method: DOWN 25 SX CMT & 200# HULLS. PERFORATE AT 1000'. CIRCULATE CMT UP 8 5/8" X 5 1/2"

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/09/2001 9:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3302-06', 3364-67', 3461-64'. BOTTOM PLUG PUMP 25 SX CMT & 200# HULLS. DISPLACED TO 3050'. PERFORATED 5 1/2" AT 1000'. PUMPED 255 SX CMT DOWN 5 1/2" CASING CIRCULATING CMT UP 8 5/8" X 5 1/2" ANNULUS TO SURFACE.

INVOICED  
DATE 3-20-2001  
INV. NO. 2001661520

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Steen K. [Signature] for RWK  
(TECHNICIAN)

KS