

To: 1 052108 2-20
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202 K-165-30138-0000

API NUMBER 15- 3/3/66
NW SE SW, SEC. 29, T 16 S, R 16 W/E
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3456
Operator: AFG Energy Inc.
Name & Address: P.O. Box 458
Hays, KS 67601

Lease Name Allen B Well # 2
County Rush 116.35
Well Total Depth 3580 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 20 Month: 2 Year: 19 97

Plugging proposal received from Ed Glassman
(company name) AFG Energy Inc. (phone) 913-625-6374

were: 4 1/2" at 3099' w/150 sx cement, PBD 3063', Perfs at 2996-3002', DV @ 1070' w/550 sx cement
1st plug fill 4 1/2" casing with cement,

Check backside.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45 a.m. Day: 20 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 500 lbs. hulls and 225 sx cement.
Maximum pressure 1200 psi and shut in 600 psi.

Casing was sitting on a hanger. Company to check 8 5/8" X 4 1/2" cement top when head is cut-off.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to reserve this plugging.

DATE 2-25-97
INV. NO. 47656
2-20

Signed Richard W. Lacey (TECHNICIAN)