

1052421

TO: STATE CORPORATION COMMISSION

API NUMBER 15-165-20,788 -0000  
SE SE NW SEC. 22, T 16 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WEGELE WELL # 1

TECHNICIAN'S PLUGGING REPORT

8/18

COUNTY RUSH 114, 56

OPERATOR LICENSE # 9370

WELL TOTAL DEPTH 3525 FEET

OPERATOR: KAL OIL OPERATIONS

PRODUCTION CSG: SIZE 5 1/2" @ 3525' WITH SX

NAME AND 18808 MICHAELIS TERRACE

SURFACE CASING: SIZE 8 5/8" @ 1034' WITH SX

ADDRESS RUSSELL, KS 67665

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:45 PM DAY: 18 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 3458-62

SAND BACK TO 3400' & 5 SX CEMENT. 1ST PLUG AT 1040' WITH 50 SX CEMENT. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 18 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

SAND TO 3320' & 5 SX CEMENT. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1040' WITH 10 SX GEL - 50 SX CEMENT - 2 SX GEL. 2ND PLUG AT 400' WITH 50 SX CEMENT. 3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2231' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

**INVOICED**

SIGNED

Richard W. Lucy  
(TECHNICIAN)

DATE 9/26/00

INV. NO. 2001060636

RECEIVED  
STATE CORPORATION COMMISSION

AUG 28 2000

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
*(Signature)*