

1 070895

15 ~~15~~ 00330-0000
165

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/22/64

NE NE SE, SEC. 32, T 16 S, R 16 W/EX

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Allen Well # 1

Operator: AFG Energy, Inc.

County Rush 116.51

Name & Address P.O. Box 605

Well Total Depth 3585 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor AFG Energy, Inc. License Number 3456

Address P.O. Box 605, Russell, KS 67665

Company to plug at: Hour: 9:45 a.m. Day: 14 Month: 12 Year: 19 90

Plugging proposal received from Terry Piesker

(company name) AFG Energy, Inc. (phone) 913-483-6213

were: 4 1/2" at 3111' w/150 sx cement, CIBP at 2850', Perfs at 2997-3002' DV at 1116' w/550 sx cement to 0
1st plug pump through tubing at 2804' with 90 sx cement,

2nd plug pull tubing to 1800' and pump 75 sx cement,

3rd plug pull to 800' and pump 20 sx cement to 0', 4th plug pump 10 sx cement down 4 1/2",

5th plug pump 30 sx cement down backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:05 p.m. Day: 14 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped through tubing at 2804' with 90 sx cement,

2nd plug pulled tubing to 1800' and pumped 75 sx cement,

3rd plug pulled to 800' and pumped 20 sx cement to 0',

4th plug pumped 10 sx cement down 4 1/2", Maximum pressure 1000 psi and shut in 500 psi.

5th plug pumped 30 sx cement down backside, Maximum pressure 1000 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

DEC 19 1990

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-8-91

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 30388