

1060126 TO: 10-9 API NUMBER 15-165-21,668-0000
STATE CORPORATION COMMISSION 175' SW of C SE NW SEC. 3, T 16 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 3176 FEET FROM SOUTH SECTION LINE
WICHITA STATE OFFICE BLDG., 130 S. MARKET 3424 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HERL TRUST WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY RUSH 118.63

OPERATOR LICENSE # 31741 WELL TOTAL DEPTH 3650 FEET

OPERATOR: LIBOC, INC PRODUCTION CSG: SIZE 5 1/2 " FEET 3649

NAME AND 16430 PARK TEN PL DR, STE 600 SURFACE CASING: SIZE 8 5/8 " FEET 1115'

ADDRESS HOUSTON, TX 77084

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 08 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KEN

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 3507-3511

1ST PLUG PUMP 25 SX CEMENT TO BOTTOM,

2ND PLUG AT 1150' WITH 50 SX CEMENT,

3RD PLUG AT 500' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 08 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG PUMPED 25 SX OF COMMON CEMENT TO BOTTOM,

2ND PLUG AT 1150' WITH 50 SX CEMENT,

3RD PLUG AT 500' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2075' OF 5 1/2" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael G. Maier (TECHNICIAN) FORM CP-2/3

10-19-98
60119

98
10-16-98