

To: 1 052158 8-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 165-21,650-0000
SW NE SW, SEC. 3, T 16 S, R 18 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 31741
Operator: Liboc, Inc.
Name:
Address 3300 S. Parker Rd., Ste. 206
Aurora, CO 80014

Lease Name Grabbe Well # 1
County Rush 118.30
Well Total Depth 3640 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1101

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Paramount Enterprises, Inc. License Number 3763
Address P.O. Box 861, Hays, KS 67601-0861

Company to plug at: Hour: 9 a.m. Day: 16 Month: 8 Year: 1997

Plugging proposal received from Ron Geist
(company name) Paramount Enterprises, Inc. (phone) 913-628-1099

logs: 5 1/2" at 3639' w/110 sx cement, PBSD 3540', Perfs at 3512-14'
1st plug sand back to 3450' and dump 5 sx cement on top of sand through bailer,
2nd plug at 1100' with 50 sx cement, 3rd plug at 500' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 16 Month: 8 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3450' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through casing:
2nd plug at 1100' with 10 sx gel and 50 sx cement,
3rd plug at 500' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2583' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

I (lib/XXXXXXXX) observe this plugging.

DATE 8-27-97

Signed Richard M. Lacey
(TECHNICIAN) RWZ

INV. NO. 48864

OCT 30 1997