

1 070457

11-2-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,377-0000  
C NW NW, SEC. 17, T 16 S, R 30 W&E  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name York "HF" Well # 1

Operator: Davis Petroleum, Inc.

County Lane Lane 146.09

Name & Address Rt. 1, Box 183-B

Well Total Depth 4495 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 2 Month: 11 Year: 19 87

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4493' Perfs at 4422-36' Elevation 2750' GL

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 50 sx cement, 15 sx gel, release 8 5/8" wiper plug and pump

150 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 50 sx cement, 15 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1800' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED** (if additional description is necessary, use BACK of this form.)

DATE 11-9-87

Signed Dan Goodera  
(TECHNICIAN)

INV. NO. 18762