

1 060013

2-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,543-0000  
SW SE NW, SEC. 15, T 16 S, R 30 W/R  
2970 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Watt "CC" Well # 1

Operator: Slawson Exploration Company, Inc.  
Name & Address 104 South Broadway, Suite 200  
Wichita, KS 67202-4165

County Lane Lane 147.88  
Well Total Depth 4550 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 4:15 a.m. Day: 21 Month: 2 Year: 19 90

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2786'  
Anhydrite 2185-2215'

1st plug at 2220' with 50 sx cement, 2nd plug at 1420' with 80 sx cement,  
3rd plug at 380' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 7 a.m. Day: 21 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement,  
2nd plug at 1420' with 80 sx cement,  
3rd plug at 380' with 40 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

223-90

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not) observe this plugging.

DATE 2-26-90

Signed Case Morris  
(TECHNICIAN)

INV. NO. 27525

APR 17 1990