

To: 1 030600
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,251-0000 *R*

NW SE NE, SEC. 21, T 16 S, R 30 W/EX

3620 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Cramer 'EE' Well # 1

Operator: Slawson, Donald C.

County Lane 148.36

Name &

Address 200 Douglas Building

Well Total Depth 4565 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well Input Well SWD Well D&A ☒

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, Broadway and Douglas, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 2 Month: December Year: 19 85

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2812'
Anhydrite 2214'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ☒

Operations Completed: Hour: 1:30 am Day: 3 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2240' with 50 sx cement, 2nd plug at 1320' with 75 sx

cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

10/16/85 I hereby certify that I have reviewed this plugging.

STATE CORPORATION COMMISSION

DATE DEC 16 1985

Signed Steve Plummer
(TECHNICIAN)

IV. NO. 11534

12-3

DEC 5 1985
12-5-85
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84