

5 020196

15-159-00622-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 7/24/69

~~NE/NW/~~ SEC. 21, T. 21 S. R. 10 W/4

4950 feet from N(S) section line

4290 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Boy Well # 1

Operator: Lebsack Oil Production, Inc.

County Rice 112.06

Name & Address Box 489

Well Total Depth 3448 feet

Hays, Kansas 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/8 feet 204

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 12 Month: August Year: 1985

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3320 and cement with 5 sacks.

Squeeze hole with 5 sacks hulls, 20 sacks Bentonite, 8 3/8" plug, and 100 sacks 60/40 Permox w/4% gel. Pump into 8 3/8" surface casing

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 AM Day: 12 Month: August Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with sand to 3320 and cemented with 5 sacks cement. Hole Squeezed with 5 sacks hulls, 20 sacks Bentonite, 8 3/8" plug, and 100 sacks 60/40 Permox w/4% gel pumped into 8 3/8" surface casing.

Max. Pressure 600 PSIG Close in press. 500 PSIG 1400' OF 5 1/2" recovered.

Remarks: 5 1/2" - 3447' - 225 sacks PerF 3372-74 Filled # 40118
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE 8-20-85

Signed [Signature]
(TECHNICIAN)

INV. NO. 9696

AUG 20 1985