

1 070648

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,647-8000
NE SE NE, SEC. 13, T 16 S, R 30 W 1/4
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3476
Operator: Moff Oil Company
Name & Address: 318 North Ninnescaw
Pratt, KS 67124

RECEIVED
STATE CORPORATION COMMISSION
3-2-89
MAR 00 1989

CONSERVATION DIVISION
Wichita, Kansas

Lease Name Roemer Well # 5
County Lane 146.40
Well Total Depth 4520 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 2 Month: 3 Year: 1989

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4499' Perfs at 4421-32'

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer,

2nd plug shoot casing at 1200' and pump 25 sx cement, 3rd plug shoot casing at 1000' and

pull up to 900 and pump 5 sx gel and 50 sx cement, 4th plug pull to 400' and pump 40 sx

cement, 5th plug pull to 40' and pump 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 p.m. Day: 2 Month: 3 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of sand through bailer.

2nd plug shot casing at 1200' and pumped 25 sx cement,

3rd plug shot casing at 1000' and pulled up to 900' and pumped 5 sx gel and 50 sx cement,

4th plug pulled to 400' and pumped 40 sx cement,

5th plug pulled to 40' and pumped 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 995' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-20-89

INV. NO. 24156

Signed Dan Goodrow (TECHNICIAN)