

3-7

To: 1 031020
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,543-0000
SW SE NE, SEC. 13, T 16 S, R 30 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3476

Operator: Moff Oil Company
Name & Address: 318 N. Ninnescah
Pratt, KS 67124

2970 feet from S section line
990 feet from E section line

Lease Name Roemer Well # 1
County Lane 148.53

Well Total Depth 4570 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 3 5/8 feet 323

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: _____ Day: 3 Month: 3 Year: 19 89

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4564' Perfs at 4400-05'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 25 sx cement at 1205', displace to 1200',

3rd plug pump 50 sx cement at 806', 4th plug pump 40 sx cement at 400',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: _____ Day: 7 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 25 sx cement at 1205', displaced to 1200',

3rd plug pumped 50 sx cement at 806',

4th plug pumped 40 sx cement at 400',

5th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel. Recovered 806' 4 1/2" casing.
(if additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1989
7-31-89
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED (do not) observe this plugging.

DATE 8-1-89

Signed Steve Durrant (TECHNICIAN)

INV. NO. 25481

3-7 AUG 10 1989 NOV 06 1989