

3-8 88 R

To: 1 070650
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,584 -0000
SE SW NW, SEC. 13, T 16 S, R 30 W/E
2970 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3476
Operator: Moff Oil Company
Name & Address: 318 North Ninnescah
Pratt, KS 67124
Well Name: Roemer B Well # 1
County: Lane
Well Total Depth: 4401 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 326

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1989
3-21-89
CONSERVATION DIVISION
Wichita, Kansas

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Kelso Casing Pulling, Inc. License Number 6050

Address: P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:40 a.m. Day: 8 Month: 3 Year: 1989

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4387' PBT 4399' Perfs at 4387-99'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 25 sx cement at 1200',

3rd plug pump 5 sx gel and 50 sx cement at 900', 4th plug pump 40 sx cement at 400',

5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 8 Month: 3 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300',

2nd plug shot casing at 1200' and pumped 25 sx cement,

3rd plug shot casing at 900' and pumped 5 sx gel and 50 sx cement,

4th plug pulled casing to 400' and pumped 40 sx cement,

5th plug pulled casing to 40' and pumped 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 900' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 3-23-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 24202