

To: 1 120987  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-17

API NUMBER 15- 165-21,645-0000 R  
S/2 NE NW, SEC. 28, T 16 S, R 16 W/E  
4290 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456  
Operator: AFG Energy Inc.  
Name: \_\_\_\_\_  
Address P.O. Box 458  
Hays, KS 67601

Lease Name Kaiser A Well # 2  
County Rush 116.35  
Well Total Depth 3580 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1075

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_  
Address Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 17 Month: 11 Year: 19 94

Plugging proposal received from Terry Piesker

(company name) AFG Energy Inc. (phone) 913-625-6374

were: 4 1/2" at 3563' w/150 sx cement, PBTD 3524', Perfs at 3292-95, 3276-80, 3219-22'

1st plug pump in 4 1/2" casing with 300 lbs. hulls and 155 sx cement,

2nd plug pump in 8 5/8" X 4 1/2" annulus with 200 lbs. hulls and 200 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:40 a.m. Day: 17 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 300 lbs. hulls and 155 sx cement.

Pumping pressure 0-1000 psi and shut in 500 psi.

2nd plug pumped in 8 5/8" X 4 1/2" annulus with 200 lbs. hulls and 200 sx cement.

Pumping pressure 0-800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  Reserve this plugging.

Signed Duane Rankin  
(TECHNICIAN)

DATE 11-29-94  
WFL NO. 41732