

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 6/18

LEASE NAME Girod

WELL NUMBER B 1

SPOT LOCATION SW SE SE

SEC. 25 TWP. 25 RGE. 4 (E) or ~~XXX~~

COUNTY Butler

Date Well Completed 6/78

Plugging Commenced 2/24/89

Plugging Completed 2/28/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR HAWKINS OIL & GAS
c/o United Cement & Acid
ADDRESS PO Box 712 El Dorado, Kansas 67042

PHONE 316 321/4680 OPERATORS LICENSE NO. 6378

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 2574'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	210'	0
				5 1/2"	2574'	1139'

RECEIVED
STATE CORPORATION COMMISSION
3-3-89
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Moved to Girod Bl. Run tools to 2500'. Plugged back with rock from 2500' to 2430'. Mix & dump 6 sacks cement @ 2430'. Ripped 5 1/2" csg @ 1675'. United pumped 70 BBLs water down 5 1/2" csg. Couldn't pull pipe. Ripped 5 1/2" csg @ 1450', 1250', 1139' & 1075'. Pulled 35 jts 5 1/2" csg 1139'. Run 9 jts 2 3/8" tubing 270'. United circulated 101 sacks 65/35 pozmix cement + 2% gel (If additional description is necessary, use BACK of this form.) OVER

Name of Plugging Contractor W W DRILLING CO. License No. 6012
Address RR # 3 Box 66 El Dorado, Ks. 67042

STATE OF Kansas COUNTY OF Butler, ss.

Dale Wilson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of above-described well as filed that the same are true and correct. Help me God.

(Signature) Dale Wilson

(Address) RR #3 Box 66 El Dorado, Kansas 67042

Emma R. Utterback
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES 11-12-91

My Commission expires:

SWORN TO before me this 2 day of March, 1989
Emma R. Utterback
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 03 1989

CONSERVATION DIVISION
Wichita, Kansas

from 270' to surface. Pulled tubing. Rigged down.