

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-24,7470000

LEASE NAME Lawrence

WELL NUMBER 3

1,650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 25 TWP. 13 RGE. 12 ~~XXX~~ (W)

COUNTY Barton

Date Well Completed 2-10-03

Plugging Commenced 2-10-03

Plugging Completed 2-10-03

RECEIVED

FEB 20 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, Kansas 67601

PHONE/(785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-10-03 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,404'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	282'	Cmtd. w/215 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 3,380', pump 25 sax cement down drill pipe. Push bridge plug to 685', Pump 25 sax cement down drill pipe. Push bridge plug to 350', pump 50 sax cement down drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. Contractor  
(Employee of ~~operator~~) or ~~(operator)~~  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 17th day of February ~~xxx~~2003

My Commission Expires:



Notary Public



Shields


15-009-24747-0000

Russell, Kansas

WELL LOG

Operator: R.P. Nixon Operations, Inc.  
 Well: Lawrence #3  
 Commenced: February 4, 2003  
 Completed: February 11, 2003  
 Contractor: Shields Drilling Co.

Well Description: SW NE SE  
 Sec. 25-18S-12W  
 Barton County, KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	282'	Cmtd. w/215 sax

Elevation: 1,809' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Sand & shale	665'	
Shale	674'	
Anhydrite	693'	
Shale	2,545'	
Shale & lime	2,718'	
Shale	2,880'	
Shale & lime	3,015'	
Lime	3,404'	RTD

RECEIVED  
 FEB 20 2003  
 KCC WICHITA

Notes