

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20310-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 22-17S-27W  
998 feet from N Section Line, 1645 feet from W Section Line  
Lease Name: WHEATCROFT GLEN C Well #: 5  
County: LANE Total Vertical Depth: 4555 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT	5.5	2055		WITH 500 SX CMT
PROD	5.5	4554	0	WITH 500 SX CMT
SURF	8.625	313		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2012 9:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: BERNIE RUNDSTROM Company: WILTON PETROLEUM Phone: (620) 628-4466

Proposed Plugging Method: COVER PERFS WITH SAND TO 4145' & 5 SX CMT. PLUG AT 2100' WITH 50 SX CMT, 650' WITH 50 SX CMT, 40' WITH 10 SX CMT. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2012 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 4492' & PUMPED 50 SX CMT & 150# HULLS. 1ST PLUG PULL TBG TO 2100' & PUMP 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CIRCULATED CMT. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED 250# & HELD.

Perfs:

Top	Bot	Thru	Comments
4208	4214		
4198	4202		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Michael Maier*  
10/10/12

(TECHNICIAN)

RECEIVED  
OCT 10 2012  
KCC DODGE CITY

RECEIVED  
OCT 15 2012  
KCC WICHITA

AMC