

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21923-00-00
Spot: SESENW Sec/Twnshp/Rge: 8-20S-24W
2219 feet from N Section Line, 2342 feet from W Section Line
Lease Name: BETZ C Well #: 2
County: NESS Total Vertical Depth: 4367 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4346	0	WITH 250 SX CMT
SURF	8.625	287		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2012 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND TO 4300' & 5 SX CMT. PRESSURE CASING TO 300#. IF HOLDS PERFORATE @ 750' & PUMP 80 SX CMT OVER CASING VOLUME. BRING 150 SX CMT FOR BACKSIDE. IF DOES NOT HOLD PRESSURE SET HOT PLUG AT 1580' & PRESSURE TO 300#.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2012 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****SQUEEZED HOLE AT 2247' W/150 SX CMT** SANDED BOTTOM TO 4308' WITH 2 SX CMT. TEST CASING, DID NOT HOLD. PUMP 50 SX CMT W/3% CC AT 1550'. WAIT ONE HOUR. TEST CASING. HELD. PERFORATE AT 750'. RUN TBG TO 750' & PUMP 115 SX CMT. CMT CIRCULATED. PULL TBG & TIED ONTO CASING. PUMP 80 SX CMT NO PRESSURE. TOPPED OFF WITH 90 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.**

Perfs:

Top	Bot	Thru	Comments
4346	4367		

RECEIVED
OCT 15 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed

Michael Maier
10/23/12 (TECHNICIAN)

RECEIVED
OCT 15 2012
KCC WICHITA