

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23359-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 24-34S-13W
1423 feet from N Section Line, 1723 feet from W Section Line
Lease Name: CUNDIFF Well #: 1
County: BARBER Total Vertical Depth: 5330 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5230	3600	WITH 180 SX CMT
SURF	10.75	250		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/09/2012 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 30 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2012 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 30 SX CMT. DISPLACED TO 4500'. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 400#. 1ST PLUG AT 610' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4850	4862		MISSISSIPPIAN
4818	4830		MISSISSIPPIAN
4770	4794		MISSISSIPPIAN
4760	4862		MISSISSIPPIAN

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

RECEIVED
OCT 18 2012
KCC WICHITA

District: 01

Signed Stephen J Pfeifer
10/22/12 (TECHNICIAN)

RESERVED
KCC WICHITA

Handwritten mark