

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20844-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 24-28S-23W
930 feet from N Section Line, 800 feet from E Section Line
Lease Name: CLEVENGER Well #: 1-24
County: FORD Total Vertical Depth: 5350 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	642		WITH 320 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/27/2012 2:45 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: WALT PURCELL Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: IST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 09/27/2012 4:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

IST PLUG AT 1550' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Michael Maier
10/20/12 (TECHNICIAN)

RECEIVED
OCT 11 2012
KCC WICHITA