

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00462-0011
Spot: SESESW Sec/Twnshp/Rge: 8-21S-1W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CHAVEZ Well #: 1
County: MCPHERSON Total Vertical Depth: 3493 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------|
| CIBP | | 300 | | KINDERHOOK |
| CIBP | | 3419 | | VIOLA |
| COND | 3.5 | 328 | | 100 SX |
| PROD | 4.5 | 3493 | | 150 SX |
| SURF | 8.625 | 170 | | 125 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/14/2012 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Revd. from: DOUGLAS D LOEWEN Company: _____ Phone: (620) 628-4425

Proposed Plugging Method: AS PER KCC DISTRICT #2

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 05/15/2012 11:55 AM KCC Agent: HUNTER CLARK

Actual Plugging Report:

5/14/2012, RAN 2 1/16" TUBING DOWN TO 3006' SPOTTED 50 SX PLUG. HIT PLUG AT 2468'. SHOT CASING AT 400'. 4 SHOTS FROM 400 TO 401', RAN TUBING DOWN TO 400' CIRCULATED WATER THEN PUMPED 265 SX OF 60/40 4% TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 3369 | 3371 | | MISNER |
| 2983 | 2985 | | MISSISSIPPI |
| 2969 | 2973 | | MISSISSIPPI |
| 2963 | 2963 | | MISSISSIPPI |

RECEIVED
OCT 22 2012

KCC WICHITA

Remarks: COPELAND CEMENT TICKET #37917. PLUGGED DUE TO COMMISSION ORDER.

Plugged through: TBG

District: 02

Signed Hunter Clark (TECHNICIAN)
10/23/12